

VAN DE WIELE & VOGLER, INC.
BID TABULATION

Katy Creek Ranch Section Six
Back Lot Retaining Wall
within Harris-Fort Bend Counties MUD No. 5
Fort Bend County, Texas
V&V Project Number: 12503-006-2-UTL
Bid Date: Friday, July 30, 2010

ITEM NO.	DESCRIPTION	UNIT	BID QTY	1. SMG Concrete Pavers, Inc.		2. Lonnie Lischka Company, LP		3. L.N. McKean, Inc.	
				UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
<u>KATY CREEK RANCH, SECTION SIX-BACK OF LOT RETAINING WALL</u>									
1.	Concrete Retaining Wall w/o Surcharge Load Including wall and 3'-10" Footing slab, Drainage Gravel Wrapped with Filter Fabric, Weep Holes, Hardware Cloth, Rebar, Expansion Joints, Construction Joints and Excavation needed to construct the wall Complete In Place per plans and specifications)	LF	645	\$ 75.00	\$ 48,375.00	\$ 90.30	\$ 58,243.50	\$ 125.00	\$ 80,625.00
2.	Concrete Retaining Wall w/ Surcharge Load (Including wall and 4'-10" Footing slab, Drainage Gravel Wrapped with Filter Fabric, Weep Holes, Hardware Cloth, Rebar, Expansion Joints, Construction Joints and Excavation needed to construct the wall Complete In Place per plans and specifications)	LF	426	\$ 104.00	\$ 44,304.00	\$ 94.71	\$ 40,346.46	\$ 129.00	\$ 54,954.00
3.	Turf Establishment of Disturbed Area	Acre	0.30	\$ 1,500.00	\$ 450.00	\$ 4,000.00	\$ 1,200.00	\$ 3,700.00	\$ 1,110.00
GRAND TOTAL BID AMOUNT KATY CREEK RANCH, SECTION SIX BACK LOT RETAINING WALL					\$ 93,129.00		\$ 99,789.96		\$ 136,689.00
TOTAL BID					\$93,129.00		\$99,789.96		\$136,689.00
CALENDAR DAYS					60		60		45
ADDITIONAL BIDS:				Menade Inc. \$137,505.00 60 Calendar Days T&C Construction \$153,060.00 90 Calendar Days Jerdon Enterprises, L.P. \$153,153.53 60 Calendar Days Tidal Construction \$172,302.00 150 Calendar Days Harris Construction Company, Ltd. \$173,400.00 90 Calendar Days Triple B Services, L.L.P. \$172,995.00 48 Calendar Days C&D Constructors Inc. \$185,796.72 45 Calendar Days Gitesh Desai \$309,540.00 45 Calendar Days					